





## Wizzer by A.D.M

### Set-up

	<ul style="list-style-type: none"> <li>Locate level and firm ground with a diameter of approx. 20 foot.</li> </ul>
	<ul style="list-style-type: none"> <li>Unhook ride from towing vehicle when it is place in operating location</li> </ul>
	<ul style="list-style-type: none"> <li>Level the ride with the four frame jack stands set on wood blocking.</li> </ul>
	<ul style="list-style-type: none"> <li>Remove tongue from hitch and store on trailer</li> </ul>
	<ul style="list-style-type: none"> <li>Remove fence elements from racks on the ride and set up in approx. 20 foot diameter circle from the center of the ride</li> </ul>
	<ul style="list-style-type: none"> <li>Remove transport racks and store</li> </ul>
	<ul style="list-style-type: none"> <li>Unpin tub from transport holder and return pin to holder with hair pin</li> </ul>
	<ul style="list-style-type: none"> <li>Check perimeter fence for clearance</li> </ul>

### Daily Preopening Checklist (To be performed by the operator)

	<ul style="list-style-type: none"> <li>View the whole ride from the entrance gate, look for anything unusual</li> </ul>
	<ul style="list-style-type: none"> <li>Check for overall cleanliness</li> </ul>
	<ul style="list-style-type: none"> <li>Inspect the perimeter fencing, adjust and repair as needed.</li> </ul>
	<ul style="list-style-type: none"> <li>Check for proper clearances to the ride</li> </ul>
	<ul style="list-style-type: none"> <li>Check the inside of the perimeter for obstructions and sharp objects on the ground</li> </ul>
	<ul style="list-style-type: none"> <li>Check for holes or bumps on the ground where patrons could stumble and fall</li> </ul>
	<ul style="list-style-type: none"> <li>Check the signs at the entrance. Are they adequate, visible, and legible for patrons to understand?</li> </ul>
	<ul style="list-style-type: none"> <li>Inspect the frame jacks, corner outriggers, and blockings. Grab hold of the tub (seat) on each side of the trailer frame. Pull down with all your weight. Try to shake the ride. Is the ride stable?</li> </ul>
	<ul style="list-style-type: none"> <li>Check for play in blocking or at the hub assembly</li> </ul>
	<ul style="list-style-type: none"> <li>Check all seats: look for bolts penetrating the seat fastened to the tub, seatbelts, and all other fasteners</li> </ul>
	<ul style="list-style-type: none"> <li>Start the ride and run through a full cycle before allowing anyone on the ride. Check for smooth operation. Investigate excessive ride vibration or unusual sounds. Report to immediate Supervisor</li> </ul>
	<ul style="list-style-type: none"> <li>Verify that a manual is on site</li> </ul>
	<ul style="list-style-type: none"> <li>Ensure all safety material is present</li> </ul>
	<ul style="list-style-type: none"> <li>Check perimeter fence for clearance</li> </ul>
	<ul style="list-style-type: none"> <li>Other:</li> </ul>

	<ul style="list-style-type: none"><li>• Comments:</li></ul>
--	---

	Print	Sign	Date
Operator			
Supervisor			